TUMKUR DIVISION.

Dated 27th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 25th October 1929, for Restoring Galaga Doddakere, Reg. No. 113, Gubbi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of September 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for Restoring Galaga Doddakere Reg. No. 113 Gubbi Taluk, "in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be cancelled, and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modifications as per data worked out during execution. For individual items of work under lump sum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract showing quantities of several items of works for restoring Galaga Doddakere Registered No. 113 of Kasaba Hobli, Gubbi Taluk.

Item No.	Particulars	Unit	Quantity
	Bund R. L. 55·00 (top width 6')		
1	Cutting grips to the slopes to receive fresh earth ...	C.yd.	As per execution
2	Jungle clearing on tank bund	Per grade	,,
3	Earthwork for embankment with watering and tamping ...	C.yd.	4,199
4	Turfing including watering till it takes root ..	S.yd.	8,015
5	Providing and fixing new grade stones including index stones painting with white lead and figuring with Japan, etc., complete.	Each	38
6	Providing and fixing B. M. stones including painting with white lead figuring with Japan, etc., complete ...	,,	2
7	Do Register No. stone ...	,,	1
8	Do Gauge stone	,,	1
9	Removing and resetting old stone work with new jelly ...	C.yd.	45
10	New stone work including jelly backing lead of 1½ miles, etc., complete.	,,	15
11	Putting flank bund at both ends of the weir ...	Lump sum	Rs.
	Left waste weir 70' long at R. L. 50·00.		
1	Removing sand and excavating foundation of toe wall ...	,,	,,
2	Removing and scraping uneven surface of body wall ..	Lump sum	Rs.
3	Jelly concrete in surki mortar	C.ft.	88

Item No.	Particulars	Unit	Quantity
7	Old stone work with new jelly	C.yd.	24
8	Jelly filling for apron Including collecting with a lead of 1½ miles stacking and filling, etc., complete.	,,	113
9	New rough stone work with jelly backing, etc., complete and including a lead of 1½ miles.	,,	160
10	Providing and fixing joggles	Each	6
	Right waste weir 40' long.		
1	Excavating foundation to body wall and toe wall ...	Lumpsum Rs.	
2	Burnt brick in surki mortar	C.ft.	243
3	Providing and fixing new stone slabs 6" thick dressed ...	S.ft.	45
4	Plastering with surki mortar	Sqr.	2·52
5	Old stone work with new jelly	C.yd.	26
6	Jelly for wedging to apron including collecting carting with a lead of 1½ miles stacking wedging, etc., complete ...	,,	9
7	Providing and fixing joggles	Each	3

Dated 28th September 1929.

1 Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., of 5th November 1929, for Raising the weir of Thuraganur Tank, Reg. No. 63, of Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Raising the weir of Thuraganur Tank, Reg. No. 63 of Kunigal Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality, of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

13. Part rate will be paid for any item of work at the discretion of the Executive Engineer, the payment of balance rates being reserved till the completion of work, as a guarantee that the work will be completed in the specified time.

Abstract of estimate of quantities for Raising the weir of Thuraganur Tank, Reg. No. 63 of Kunigal Taluk.

Sl. No.	Items of works	Unit	Quantity
	Bund at R. L. 59·00.		
1	Earthwork to bund, including watering, consolidation, etc., complete.	C.yd.	4166
2	Turfing including watering, till it takes root	S.yd.	5661
3	Jungle clearing over the bund	Lump sum	Rupees
4	Removing and refixing the old grade stones, including painting with white lead and figuring with Japan, etc., complete.	Each	as per execution
4a	Providing and fixing new grade stones as per approved design, including painting with white lead and figuring with Japan, etc., complete.	,,	,
5	New rough stone work for revetment including jelly filling, wedging and lead of 3 miles, etc., complete.	C.yd.	227
6	Removing and resetting the old rough stone revetment, including new jelly.	,,	200
	Sluice.		
1	Earthwork cut opening the bund	C.yd.	as per execution
1(a)	Earthwork and using earth for ring bund if necessary ..	,,	,,
2	Earthwork refilling including watering, consolidation, etc., complete.	,,	,,
2(a)	Removing earth used for ring bund and refilling the cut portion, including watering, consolidation, etc., complete.	,,	,,
3	Sundry repairs to sluice	Lump sum	Rupees
	Waste weir at R. L. 54·50.		
1(a)	Earthwork excating foundation for skin wall and using soil for bund.	C.yd.	as per execution
(b)	Removing the existing rough stone apron for building slabbed apron, including the stacking of old materials.	,,	,,
2	Burnt brick in surki mortar	C.ft.	2177
3	Plastering with surki mortar	Sqr.	25·41
4	Removing and refixing the slabs of body wall, in surki mortar	S.ft.	as per execution
5	Providing and fixing bond stones (6" thick) between skin wall and body wall.	,,	,,
6	Burnt stone jelly concrete in surki mortar	C.ft.	906
7	Providing and fixing burnt stone slabs 6" thick, dressed ...	S.ft.	2567
8	Old rough stone work, rebuilding apron with available stones at site.	C.yd.	134
9	Pointing with cement	Sqr.	25·97

V. V. PATANKAR,
Executive Engineer.

MYSORE DISTRICT.

Dated 28th September 1929.

CORRECTION SLIP.

In the notification for the sale of right of collecting and removing lops and tops of trees of the Forests of the Hunsur Range published on page 1073 of Part VI of the *Mysore Gazette*, dated 25th September 1929, against Dodharve, Mavkal, Anechowkur and Kachavanahalli coupes for the date "22-10-29", "read 21-10-29".

H. S. NARAYANA RAO,
District Forest Officer.